

GEN00022-00

FIELD ASSEMBLY INSTRUCTION

D85C-21 PIPELAYER

MACHINE MODEL	SERIAL NUMBER
D85C-21	37757 and up


KOMATSU

D85C-21

Preface

You are required to execute full inspection and maintenance before starting the engine and assembling the work equipment. Since the work is often carried out in dangerous places and positions by a team, hold a safety meeting in advance and appoint a crane director, work leader, etc. so that the all member can work safely.

When the work is carried out in an overseas country, difference in language, customs, etc. lowers safety. Accordingly, the field liaison man and work supervisor must examine the above point and take necessary measures.



We hope that the all members will cooperate with each other and assemble the work equipment quickly in the field, observing the safety, quality, and delivery time.

CONTENTS


SPECIFICATIONS.....	1
PRECAUTIONS FOR FIELD ASSEMBLY	2
ASSEMBLY PROCEDURE, NECESSARY EQUIPMENT, AND SCHEDULE.....	3
POSITION FOR TRANSPORTATION	4
LIST OF TOOLS FOR FIELD ASSEMBLY.....	7
TIGHTENING TORQUE	8
COATING MATERIALS.....	12
A. Assembly procedure	15
A-1. Installation of exhaust pipe	16
A-2. Installation of lamps	17
A-3. Installation of operator's cab	18
A-4. Installation of air conditioner	23
A-5. Installation of counterweight	26
A-6. Installation of boom.....	30
A-7. Check of oil/coolant level in each part	39
A-8. Greasing	41
M. Inspection and maintenance procedures after completion of assembly	43
M-1. Inspection and adjustment of operator's cab	44
M-2. Inspection of safety devices.....	46

FIELD ASSEMBLY INSPECTION REPORT

SPECIFICATIONS

Item	Unit	D85C-21
Operating weight (excluding operator)	kg	30,210 *1
Weight of boom unit (Length: 7,300 mm)	kg	1,080
Weight of counterweight unit (including cylinder and weight)	kg	5,995
Engine name	–	KOMATSU S6D125-2 Diesel engine
Rated engine output	kW/rpm {HP/rpm}	168/2,000 {225/2,000}
Rated engine torque	Nm/rpm {kgm/rpm}	1,000/1,400 {102/1,400}
Travel speed (1st/2nd/3rd)	Forward km/h	3.5/6.5/10.7
	Reverse km/h	4.7/8.3/13.3
Hook speed (Converted in to speed of bare drum)	Winding-in m/min	9.6/21.7
	Winding-out m/min	9.3/21.1

*1: 6.2 m long boom, 610 mm shoe, with cab



PRECAUTIONS FOR FIELD ASSEMBLY

1. Selection of workplace

- 1) When selecting a workplace, consider the following items so that you can load and unload the machine.
 - Width
 - Hardness
 - Flatness
 - Access road, place for turn
- 2) Do not work in a place where dust, rainwater, etc. may enter the hydraulic circuit during assembling work.
- 3) Do not assemble while a strong wind is blowing or it is raining.

2. Preparation and check of slings and tools

- 1) Check each sling and tool thoroughly. When using wood blocks, etc., check that their inside is not rotten or broken.

3. Check of actual work

- 1) Apply the parking brakes of the trailer and crane truck securely and put chocks under their wheels.
- 2) Before starting the work lower the temperature and pressure of the engine oil, hydraulic oil, cooling water, etc.
- 3) When starting the engine, make an arranged sign such as sounding of the horn and check that the work equipment control lever and travel lever are in neutral and the fuel control dial (or fuel control lever) is at the low idling position.
- 4) When using the crane, balance the load.
- 5) Allow only the persons concerned into the workplace.

4. Before starting the work, read this manual thoroughly and keep the precautions in your mind.

5. The supervisor shall write down the precautions for each work process and explain them to the workers.

6. Hold a meeting every morning to check today's work plan and safe work.

ASSEMBLY PROCEDURE, NECESSARY EQUIPMENT, AND SCHEDULE

	1st day		2nd day		3rd day	
	AM	PM	AM	PM	AM	PM
Unloading from trailer	Installation of exhaust pipe		Supply of grease on counterweight side Check of operation of counterweight and supply of oil	Installation of hook Winding of hook wire	Assembly inspection • Check of oil and water levels and operating functions • Check of revolution of engine • Check for abnormal sound and smell	
Installation of lamps • Installation of cab sub-assembly (Lamps and accessories)		Installation of counterweight • Installation of bracket, large link, small link, and cylinder to chassis sub-assembly • Installation of hoses • Installation of weight	Installation of boom Installation of upper sheave block Installation of hook sheave block	Check of operation of completed machine	Correction Washing of machine	
Removal of rust-preventive paint from chassis	Installation of cab	Piping of air conditioner and heater Wiring Charging air conditioner with refrigerant	Winding of boom wire Installation of angle indicator Installation of overwind device Installation of overwind wiring harness	Test operation	Touch-up painting	
Collection of parts packed separately						
Wrecker truck	20 ton × 1 unit	→	20 ton × 1 unit	→	20 ton × 1 unit	→
Working time	6 H		6 H		7 H	
Number of	3		3		3	
Working time	18 H		18 H		21 H	
			Total		57 H	